



PERFORMANCE TEST REPORT

Air Permeability, Watertightness and Resistance to Wind Load

Test Report No: 010.059.1 / 2012



Rendered to	: Burak Alüminyum San. ve Tic. Ltd. Şti.	Norms Applied	: EN 12153
			: EN 12155
			: EN 12179
Product	: AG 50		:
		Classification Norms	: EN 12152
			: EN 12154
			: EN 13116
Sample Size	: 4050 mm x 5600 mm		:
Sample Description	: Curtain Wall		:
	: 6 / 21 / 4 + 0,76 + 4 Insulated Glass		:
	: Four Sided	Test Comp. Date	: 10.01.2012
Test Performed	: Air Permeability - Static	Report Date	: 13.01.2012
	: Watertightness - Static	Record Retention Date	: 13.01.2017
	: Wind Resistance - Static	Number of Pages	: 10
		Number of Annex Pages:	6


Test Results : The Test sample performed in accordance of to following classifications

Air Penetration	: EN 12152 - Class A4 (600 Pa)
Water Tightness	: EN 12154 - R5 (300 Pa)
Wind Resistance	: EN 13116 - FAIL (23,79 mm > 15 mm, -21,02 mm > 15 mm)
Wind Resistance	: EN 13116 - OK (Extreme Load)

* Calibration of the test equipments certified by CEBTP / France referenced to report BEB1-B.2013-1 and BEB1-B.2013-2

**This Test Report includes specific test data, results, photographic documentation and build drawings of the sample submitted for testing only and thus does not prejudice other related products.


Oktay Usta
Testing Manager


M. Sernat Golak
Testing Engineer



CONTENTS

1. PREFACE	2
2. TEST PARTICIPANTS	2
3. DESCRIPTION OF TEST SAMPLE	3
4. TEST RESULTS	4
4.1 Test Conditions	4
4.2 Pressure Sequence.....	4
4.3 Air Permeability	4
4.4 Watertightness Under Static Pressure.....	6
4.5 Resistance to Wind Load	6
4.6 Increased Load Test (Safety Test - Secure Load)	9
5. REVISIONS MADE ACCORDING TO TEST RESULTS.....	9
6. RESULT.....	10
6.1. Results and Classification	10
7. ANNEXES	
7.1. Sample Drawings and Details	
7.2. Certification of the Calibration	
7.3. Photos taken during the test	

1. PREFACE

This report comprises of tests which were performed by FTI Façade Testing Institute at the address Çakıl Village Bağlar Region, Çatalca - Istanbul. Tests were carried out in January 2012 for the determination of the air infiltration, water penetration (static pressure) and resistance to wind loading of curtain walling systems.

The above mentioned tests have been carried out as per the test methods provided in project specifications and classified on the standards indicated below.

EN 13830	* Curtain Walling - Product Standard
EN 12153	* Curtain Walling - Air Tightness - Test Method
EN 12152	* Curtain Walling - Air Tightness - Performance Requirements and Classification
EN 12155	* Curtain Walling - Water Tightness - Laboratory Tests Under Static Pressure
EN 12154	* Curtain Walling - Water Tightness - Performance Requirements and Classification
EN 12179	* Curtain Walling - Resistance to Wind Load - Test Method
EN 13116	* Curtain Walling - Resistance to Wind Load - Performance Requirements

Test sample comprises of a part of façade system which have been constructed for Autoport Project by Burak Alüminyum San. Ve Tic. Ltd. Şti.

Test sample was prepared by the company's own facilities and has been sent to FTI Façade Testing Institute's testing laboratories on 02 / 12 / 2012.

2. TEST PARTICIPANTS

Tests were conducted on 10 / 01 / 2012 with the following participants.

Mr. Oktay USTA	FTI	Testing Manager
Mr. Öner ARSLAN	FTI	Testing Engineer
Mr. M.Serhat ÇOLAK	FTI	Testing Engineer
and partially by Ali ÇOLAK	Burak Alüminyum	

3. DESCRIPTION OF TEST SAMPLE

* Type of Sample	Curtain Wall
* System	AG 50
* Dimensions of Sample (LxH)	4050 mm x 5600 mm
* Surface area of Sample	22,68 m²
* Fixed Panel Length	52,35 m
* Opening type	None
* Openable window	-
* Surface area of wings	- m ²
* Glass Type	6 / 21 / 4 + 0,76 + 4 Insulated Glass

System Components

* AG 753	Vertical Aluminium Profile
* AG 701	Horizontal Aluminium Profile
* Steel Reinforcement	
* Gasket	
* Silicone	

Please refer to the drawings in annexes.

4. TEST RESULTS

4.1 Test Conditions

Local Temperature	:	11,8	°C
Atmospheric Pressure	:	1011	mbar
Ambient Humidity	:	61	%
Test Stand	:	Stand	2
$\phi 1$: Flow Calculation for positive pressure	:	$0,422 \times \phi + 0,09$, while $\phi < 22 \text{ m}^3/\text{h}$ $1,525 \times \phi - 23,45$, while $\phi > 22 \text{ m}^3/\text{h}$	
$\phi 2$: Flow Calculation for negative pressure	:	$0,196 \times \phi - 0,79$, while $\phi < 25 \text{ m}^3/\text{h}$ $1,883 \times \phi - 42,42$ while $\phi > 25 \text{ m}^3/\text{h}$	

4.2 Pressure Sequence

STEPS		POSITIVE PRESSURE (Pa)	NEGATIVE PRESSURE (Pa)
1	P1=PN	600	600
2	P2=PD	600	600
3	P3=PE	900	900

PN: Pressure Normative
 PD: Pressure Design
 PE: Pressure Extreme

4.3 Air Permeability

Before starting the test, 3 pulses at 660 Pa is applied to the sample.

During the tests, the pressure at the following values is applied for 10 seconds.

Air permeability measurements based on overall area ;

POSITIVE PRESSURE			
$\phi 1 / \phi 2$	Test Pressure (Pa)	Air Leakage (m ³ /h)	Air Leakage (m ³ /h/m ²)
$\phi 1$	50	0,52	0,02
$\phi 1$	100	1,95	0,09
$\phi 1$	150	4,27	0,19
$\phi 1$	200	4,88	0,22
$\phi 1$	250	7,11	0,31
$\phi 1$	300	12,16	0,54
$\phi 1$	450	15,93	0,70
$\phi 1$	600	29,61	1,31

Test No : 2011.131.07

NEGATIVE PRESSURE			
$\phi 1 / \phi 2$	Test Pressure (Pa)	Air Leakage (m ³ /h)	Air Leakage (m ³ /h/m ²)
$\phi 1$	50	0,36	0,02
$\phi 1$	100	1,02	0,04
$\phi 1$	150	1,77	0,08
$\phi 1$	200	2,20	0,10
$\phi 1$	250	2,26	0,10
$\phi 1$	300	2,53	0,11
$\phi 1$	450	12,81	0,56
$\phi 1$	600	18,02	0,79

Test No : 2011.131.08



Air permeability measurements based on fixed joint length;

POSITIVE PRESSURE			
$\phi 1 / \phi 2$	Test Pressure (Pa)	Air Leakage (m ³ /h)	Air Leakage (m ³ /h/m)
$\phi 1$	50	0,52	0,01
$\phi 1$	100	1,95	0,04
$\phi 1$	150	4,27	0,08
$\phi 1$	200	4,88	0,09
$\phi 1$	250	7,11	0,14
$\phi 1$	300	12,16	0,23
$\phi 1$	450	15,93	0,30
$\phi 1$	600	29,61	0,57

Test No : 2011.131.07

NEGATIVE PRESSURE			
$\phi 1 / \phi 2$	Test Pressure (Pa)	Air Leakage (m ³ /h)	Air Leakage (m ³ /h/m)
$\phi 1$	50	0,36	0,01
$\phi 1$	100	1,02	0,02
$\phi 1$	150	1,77	0,03
$\phi 1$	200	2,20	0,04
$\phi 1$	250	2,26	0,04
$\phi 1$	300	2,53	0,05
$\phi 1$	450	12,81	0,24
$\phi 1$	600	18,02	0,34

Test No : 2011.131.08



4.4 Watertightness Under Static Pressure

Before starting the test, 3 pulses at 660 Pa are applied to the sample.

Waiting duration between each impacts 3 seconds.


Water spray nozzles are arranged in 4 rows, such that the first nozzle is apart 250 mm. from the side and the distance between the nozzle rows are 1500 mm.

The number of nozzles at each row is 9 pieces.

The amount of water applied to the façade = (2 l/min x 9) x 4 = 72 l/min. = 4320 l/h

Observations

Pressure Value (Pa)	Time Period (min)	Observations
0	15	No water leakage was observed.
50	5	No water leakage was observed.
100	5	No water leakage was observed.
150	5	No water leakage was observed.
200	5	No water leakage was observed.
300	5	No water leakage was observed.
450	5	Water leakage was observed.*
600	5	Water leakage was observed.*



Test No : 2011.131.09

* Middle transom and mullion junction point.

4.5 Resistance to Wind Load

Before starting the test, 3 pulses at 600 / -600 Pa are applied to the sample.

Waiting duration between each impacts 3 seconds.

During the tests, the pressure values are applied for 10 seconds.

Acceptable proportion at resistance to wind load:

Position: Vertical distance for mullion at middle axis

Scale: **Vertical 5600 mm**

The measured frontal deflection between points of the structural support should not exceed the minimum of **1/200** of the framing member's span or 15 mm, which is smaller, under the positive and negative design loads:

Vertical 5600 / 200 = 28,00 mm or 15,00 mm

Positions of the transducers on which deflection measurements have been carried out on Test Samples



Specimen dimensions and sensor replacement coordinates;

	X coordinates (mm)	Y coordinates (mm)
External Dimensions	4050	5600
Sensor 3 Replacement	2025	5400
Sensor 2 Replacement	2025	2800
Sensor 1 Replacement	2025	200


Frontal deflection measurement results on the vertical mullion;


Positive Pressure (Pa)	Point 1 (mm)	Point 2 (mm)	Point 3 (mm)	Frontal Deflection (mm)
0	0,00	0,00	0,00	0,00
150	0,00	0,78	0,37	0,60
300	0,00	9,30	1,02	8,79
450	0,00	17,67	1,67	16,83
600	1,31	25,61	2,33	23,79
0	0,44	0,51	0,05	0,26

Test No : 2011.131.10

Negative Pressure (Pa)	Point 1 (mm)	Point 2 (mm)	Point 3 (mm)	Frontal Deflection (mm)
0	0,00	0,00	0,00	0,00
-150	0,23	1,14	0,33	0,86
-300	1,98	8,86	0,98	7,38
-450	3,84	17,50	1,70	14,73
-600	4,95	24,66	2,32	21,02
0	0,11	0,51	0,06	0,42

Test No : 2011.131.11





4.6 Increased Load Test (Safety Test - Secure Load)

Safety load increased to 1,5 times the design load is applied to the sample.

Test Pressure	Applied	Observations
PE = ± 900 Pa	± 900 Pa	No damage was observed

Test No : 2011.131.12




5. REVISIONS MADE ACCORDING TO TEST RESULTS


- No revision was made.

6. RESULT


6.1. Results and Classification

	CONDITIONS	RESULTS		CLASSIFICATION
AIR PERMEABILITY EN 12152	at 600 Pa $\phi < 1,5 \text{ m}^3/\text{h},\text{m}^2$	Positive Pressure	1,31	A4
	at 600 Pa $\phi < 0,5 \text{ m}^3/\text{h},\text{m}$		0,57	A3
	at 600 Pa $\phi < 1,5 \text{ m}^3/\text{h},\text{m}^2$	Negative Pressure	0,79	A4
	at 600 Pa $\phi < 0,5 \text{ m}^3/\text{h},\text{m}$		0,34	A4
WATER-TIGHTNESS (Static Pressure) EN 12154	There will be no water leakage at 600 Pa	Water leakage was observed at 450 Pa.		R5
RESISTANCE TO WIND LOAD EN 13116	Deflection $< 15,0 \text{ mm}$ at +600 Pa and -600 Pa	OK (max. + 23,79 mm) (max. - 21,02 mm)		FAIL
	There will be no damage at secure load (+900 Pa, -900 Pa)	No damage was observed at positive or negative pressure		OK





KESIT




PART 1

PART 2


GORUNUS


TEST YAPILACAK BOLUM -PART 2
KOORDINATLAR: (1-H)-(1-L)-(4H)-(4-L)



PLAN

TEST YAPILACAK BOLUM -PART 2
KOORDINATLAR: (1-H)-(1-L)-(4H)-(4-L)





AG 753

1,600 Kg / m



GINGER CEBTP

Entreprise:

Norm **FTI Façade Testing institute**
 Adresse **CAKIL KOYU BAGLAR MEVKII
 PK.39 CATALCA ISTAMBUL
 TURQUIE**

Division Enveloppe du bâtiment

à l'attention de M : **OKTAY USTA**

Service : Produits de l'Enveloppe

Tél. 01 30 85 23 22 Fax. 01 30 85 23 20

RAPPORT DE VERIFICATION N° : BEB1.B.2013-2
SITE: CATALCA
MYTECH 24

RECAPITULATIF des CONTRÔLES EFFECTUES PAR LE CEBTP

L'étalonnage doit être renouvelé tous les 3 ans. L'Autocontrôle doit être effectué tous les 6 mois par l'entreprise, sous sa responsabilité, afin de vérifier les dérives éventuelles du banc.

Date du Contrôle **mars-11**Prochain contrôle à faire pour **mars - 2014****CONDITIONS DE MESURES** (au début des vérifications)TEMPÉRATURE **10.0** °CHYGROMÉTRIE **38.0** %PRESSION ATMOSPHÉRIQUE **1026.0** Hpa

Pour avoir la pression atmosphérique téléphoner si nécessaire: 08 92 68 02 + N°département.

Les résultats des calculs sont à corriger en fonction des conditions réelles.

FORMULES POUR LE CALCUL DES DEBITS D'AIR

MESURES EFFECTUEES EN PRESSION						MESURES EFFECTUEES EN DEPRESSION			
N°	plage	FORMULE			formule simplifiée	N°	Diam	FORMULE	formule simplifiée
		1	0 à 65 m3/h	0.422					
2	65 à 140 m3/h	1.525	x Qb +	-23.45	1.166				

Les formules sont rapportées à T° = 20° et Patm = 101325 Pa

Planification: Auto Contrôles

L'entreprise doit avoir réalisé son auto-contrôle interne aux dates suivantes

Date	mars - 11	A
Date	août - 11	B
Date	févr - 12	C
Date	août - 12	D
Date	févr - 13	E
Date	août - 13	F

Si la dérive est > 10%, refaire le contrôle par le CEBTP, sans attendre les 3 ans

CORRECTION DES DÉBITS D'EAU

N°1		
AFFICHE	RÉEL	CORRECT
2000.0	1692.0	18%
3000.0	2720.9	10%
4000.0	3700.8	8%

Le chef de service
 Produits de l'enveloppe
 Aurélien GAUDRON

